BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2025-26/OW/WORK_INDENT7283

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/02/2025-26, Date: 09-05-2025

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
1	35.90	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge.	Cum	1920.58	Rupees One Thousand Nine Hundred Twenty and Fifty Eight Paise Only
2	47.91	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineer-in-charge. In cement mortar	Cum	1188.38	Rupees One Thousand One Hundred Eighty Eight and Thirty Eight Paise Only
3	392.53	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.machinery & other appurtenaces required to complete the work Depth exceeding 1.5m, but not exceeding 3 m	Cum	299.12	Rupees Two Hundred Ninety Nine and Twelve Paise Only
4	31.21	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specifications	Cum	3097.41	Rupees Three Thousand Ninety Seven and Forty One Paise Only
5	31.81	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes achine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other purtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	6916.14	Rupees Six Thousand Nine Hundred Sixteen and Fourteen Paise Only
6	153.70	Providing and injecting chemical emulsion for Pre-constructional Anti Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits with Chlorpyriphos 20% E.C. / Lindane 20% E.C. @ 3.19 l/m2 including cost of chemical, diluting in water to one percent concentration, labour, usage charges of machinery, complete as per specifications.	Cum	136.28	Rupees One Hundred Thirty Six and Twenty Eight Paise Only
7	91.92	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	7244.44	Rupees Seven Thousand Two Hundred Forty Four and Forty Four Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Executive Engineer

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
8	107.24	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	7793.01	Rupees Seven Thousand Seven Hundred Ninety Three and One Paise Only
9	285.29	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cm in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	181.42	Rupees One Hundred Eighty One and Forty Two Paise Only
10	131.67	Restoration of rain cuts with soil, moorum, gravel or a mixture of these, clearing the loose soil, benching for 300 mm width, laying fresh material in layers not exceeding 250 mm and compacting with plate compactor or powe	Cum	213.17	Rupees Two Hundred Thirteen and Seventeen Paise Only
11	10.97	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	7209.98	Rupees Seven Thousand Two Hundred Nine and Ninety Eight Paise Only
12	62.87	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical speci fications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) Ground Floor	Cum	10273.79	Rupees Ten Thousand Two Hundred Seventy Three and Seventy Nine Paise Only
13	56.07	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical speci fications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) First Floor	Cum	10376.52	Rupees Ten Thousand Three Hundred Seventy Six and Fifty Two Paise Only
14	32.31	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification. All other type of structures (a) Ground floor	Tonne	103312.99	Rupees One Hundred Three Thousand Three Hundred Twelve and Ninety Nine Paise Only

Signature of the Contractor

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Pa..nahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
15	10.65	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification. All other type of structures (a) First floor	Tonne	104346.12	Rupees One Hundred Four Thousand Three Hundred Forty Six and Twelve Paise Only
16	168.38	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. Ground floor	Sqm	1421.67	Rupees One Thousand Four Hundred Twenty One and Sixty Seven Paise Only
17	201.27	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specificationsFirst floor	Sqm	1435.89	Rupees One Thousand Four Hundred Thirty Five and Eighty Nine Paise Only
18	5.17	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.Mix 1:3:6 Using 20 mm nominal size graded crushed coarse aggregates FIrst floor	Cum	7251.75	Rupees Seven Thousand Two Hundred Fifty One and Seventy Five Paise Only
19	279.09	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge	Sqm	3.46	Rupees Three and Forty Six Paise Only
20	160.09	Providing 12 mm cement plaster with cement mortar 1:4 (1 cement: 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.. Ground Floor	Sqm	294.50	Rupees Two Hundred Ninety Four and Fifty Paise Only
21	160.09	Providing 12 mm cement plaster with cement mortar 1:4 (1 cement: 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. First Floor	Sqm	297.44	Rupees Two Hundred Ninety Seven and Forty Four Paise Only
22	196.87	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-Charge Ground floor inside Plastering	Sqm	408.83	Rupees Four Hundred Eight and Eighty Three Paise Only
23	196.87	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-Charge First floor inside Plastering	Sqm	412.92	Rupees Four Hundred Twelve and Ninety Two Paise Only
24	167.72	Providing 20 mm cement plaster with cement mortar 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement to brick/ stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. Ground floor	Sqm	495.45	Rupees Four Hundred Ninety Five and Forty Five Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Executive Engineer

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
25	250.95	Providing 20 mm cement plaster with cement mortar 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement to brick/ stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. Ground floor	Sqm	500.40	Rupees Five Hundred and Forty Paise Only
26	713.95	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge	Sqm	115.49	Rupees One Hundred Fifteen and Forty Nine Paise Only
27	418.66	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67L/10 m² over and including priming coat of exterior primer applied @ 2.20 kg/10 m²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge	Sqm	200.95	Rupees Two Hundred and Ninety Five Paise Only
28	713.95	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m² over and including one coat of Special primer applied @ 0.75 L/10 m² with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life)	Sqm	182.47	Rupees One Hundred Eighty Two and Forty Seven Paise Only
29	33.39	Providing skirting, dadooing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.	Sqm	1673.44	Rupees One Thousand Six Hundred Seventy Three and Forty Four Paise Only
30	9.00	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/m2 including pointing the joints with white cement and matching pigment etc., complete.	Sqm	1242.66	Rupees One Thousand Two Hundred Forty Two and Sixty Six Paise Only
31	0.17	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications GF &FF	Cum	159460.28	Rupees One Hundred Fifty Nine Thousand Four Hundred Sixty and Twenty Eight Paise Only
32	6.30	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures) Ground floor	Sqm	8597.00	Rupees Eight Thousand Five Hundred Ninety Seven Only
33	6.30	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	192.87	Rupees One Hundred Ninety Two and Eighty Seven Paise Only

Signature of the Contractor

Executive Engineer
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
34	25.20	Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge.	Rmtr	367.26	Rupees Three Hundred Sixty Seven and Twenty Six Paise Only
35	8.82	Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm for stiles and 15x15mm for top & bottom rails, covered with heat moulded PVC C channel of 5mm thick sheet & 30 x 50mm wide to form stiles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the stiles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 mm Aluminium hinges.	Sqm	1833.97	Rupees One Thousand Eight Hundred Thirty Three and Ninety Seven Paise Only
36	27.36	Providing & fixing of 3-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&Ps shall not be made	Sqm	7777.03	Rupees Seven Thousand Seven Hundred Seventy Seven and Three Paise Only
37	1.44	Providing & fixing of louvered ventilator made out of multi chambered UPVC(Matching to RAL9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free with gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the ventilator frame. The frame having overall size of 39mm x 39mm with GI reinforcement of 1mm thickness. Louver clip in Aluminium (powder coated in white) will be used on the frame along with plastic parts for fixing the 4 mm pin head glass. Wall thickness of frame shall be 2mm.Maximum possible size 1000mm x 1000mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made).	Sqm	6604.82	Rupees Six Thousand Six Hundred Four and Eighty Two Paise Only
38	146.29	Polyurethane based Single Component for New Surface Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6 kg/m2 to achieve final DFT (Dry Film Thickness) of 1mm including prime coat of epoxy primer @150 g/m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification.	Sqm	943.55	Rupees Nine Hundred Forty Three and Fifty Five Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
GBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
39	292.59	Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per direction of Engineer incharge.	Sqm	923.91	Rupees Nine Hundred Twenty Three and Ninety One Paise Only
40	179.83	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed , including cost of materials, mortar, labour, curing complete as per specifications. Ground floor	Sqm	6041.38	Rupees Six Thousand Forty One and Thirty Eight Paise Only
41	167.52	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed , including cost of materials, mortar, labour, curing complete as per specifications.First floor	Sqm	6214.79	Rupees Six Thousand Two Hundred Fourteen and Seventy Nine Paise Only
42	146.29	Providing and laying Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand) Light shade pigment using white cement	Sqm	1494.87	Rupees One Thousand Four Hundred Ninety Four and Eighty Seven Paise Only
43	2.00	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :One urinal basin with 5 litre white P.V.C. automatic flushing cistern	Each	5143.88	Rupees Five Thousand One Hundred Forty Three and Eighty Eight Paise Only
44	514.00	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	Kg	211.34	Rupees Two Hundred Eleven and Thirty Four Paise Only
45	57.60	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90 ltr/10 m² over an under coat of primer applied @ 0.80 ltr/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	160.53	Rupees One Hundred Sixty and Fifty Three Paise Only
46	303.75	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Kg	652.51	Rupees Six Hundred Fifty Two and Fifty One Paise Only

Signature of the Contractor

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
57	6.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall - 8Way	Each	274.02	Rupees Two Hundred Seventy Four and Two Paise Only
58	8.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall - 10-12 Way	Each	334.92	Rupees Three Hundred Thirty Four and Ninety Two Paise Only
59	24.00	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293.. -Stepped Fan Regulator Two Module	Each	374.81	Rupees Three Hundred Seventy Four and Eighty One Paise Only
60	24.00	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293.. -6A One Way Switch	Each	107.09	Rupees One Hundred Seven and Nine Paise Only
61	24.00	Supply of round/square recess/surface mounted rolling type LED Down light with ..... W GU 10 LED Lamp Rib Fabricated from diecast aluminium with white powder coated prewired to mains connector & has swivelling unit of aluminium die cast eye ball & LED Lamp position retained by circular wire spring, with Life of 25000 burning hours & 70% lumen maintenance with CRI 80. Power Input: 220240V @50/60Hz & Power factor 0.9 along with CE approved. 2years Warranty against any manufacturing defect working under standard electrical condition LED	Each	1390.07	Rupees One Thousand Three Hundred Ninety and Seven Paise Only
62	24.00	Supplying of Ceiling Fan with Capacitor rating As per guideline of BEE 5 star rating and IS:374/79 and also comply with IS: 1709/1984 with latest amendment, Rated voltage 220 V/50 Hz, Rated power input 48 W +/- 10 %, Rated current As per IS:374/79, Rated power factor 0.9 lagging(min), Rated speed 350 +/- 10% RPM, Rated air delivery 210 +/- 10% Cubic Meter Minimum, Rated service value 4.2 CMM / W, Three Blades of blade leaf 1.05 mm thick Aluminium Alloy sheet, Class B motor insulation, Bearing Two ball bearings, Top 6202, Bottom 6201, as per IS specification, Motor winding. Temp rise Shall not exceed 75 deg C over and ambient of 40 0C by resistance method at 245 V, Insulation resistance Shall not be less than Two Mega Ohms (2M Ohms), Leakage current Should not exceed 210 Micro Amp, Power input, W& current, Air Delivery & Fan Speed as per IS:374/1979 with latest amendment, 2 year manufacturer Warranty..48" Sweep 5 Star (1200 mm)	Each	4517.72	Rupees Four Thousand Five Hundred Seventeen and Seventy Two Paise Only
63	2.00	Supplying & fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32 A SP	Each	435.71	Rupees Four Hundred Thirty Five and Seventy One Paise Only
64	2.00	Supplying, fixing and wiring Electronic Trivector Meter (ETV) 5 to 32/63 A three phase 4 wire whole current class-1 Accuracy Energy Meter.	Each	5989.68	Rupees Five Thousand Nine Hundred Eighty Nine and Sixty Eight Paise Only
65	60.00	Supplying of 1.1KV LT UG cable XPLE or heat resistant PVC Insulated PVC eatruded inner sheath armoured UG LT cable as per IS -1554(Part-1) or IS-7098 Part-1,Armouring strip thickness in average +5% and resistivity 14ohms/kms(max) as per IS -3975 4 core 16sqmm	Rmtr	157.49	Rupees One Hundred Fifty Seven and Forty Nine Paise Only
66	60.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stone pipe / on wall/ on pole as required 6 sqmm to 16 sqmm.	Rmtr	12.47	Rupees Twelve and Forty Seven Paise Only
67	50.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete cutting road surfaces	Rmtr	86.09	Rupees Eighty Six and Nine Paise Only
68	8.00	Supplying and fixing of class A GI pipe on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm	Nos	351.72	Rupees Three Hundred Fifty One and Seventy Two Paise Only

Signature of the Contractor

Executive Engineer
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Pa. ahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
47	4.00	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. cover with frame (light duty) 600X850 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg), R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 fine sand : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand), finished smooth with a floating coat of neat cement on walls and bed concrete etc	No	8547.34	Rupees Eight Thousand Five Hundred Forty Seven and Thirty Four Paise Only
48	140.00	Supplying heavy gauge PVC conduit pipe ..... mm dia.....mm thick confirming to IS 2509 with suitable size bends, metal/PVC Junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary 25mm dia 2mm thick	Rmtr	83.99	Rupees Eighty Three and Ninety Nine Paise Only
49	120.00	Supplying heavy gauge PVC Conduit Pipe .... dia ..... mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering upto the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. 25 mm dia 2 mm thick	Rmtr	82.94	Rupees Eighty Two and Ninety Four Paise Only
50	8.00	Supplying and fixing PVC/metal conduit Deep junction box 25 mm deep Junction box	Each	59.84	Rupees Fifty Nine and Eighty Four Paise Only
51	8.00	Supplying And Fixing Metal Fan Box with Round Hook.	No	125.99	Rupees One Hundred Twenty Five and Ninety Nine Paise Only
52	6.00	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694: and latest amendments) with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. Medium point above 3m upto 6m from tapping point to out letvia switch	Point	397.91	Rupees Three Hundred Ninety Seven and Ninety One Paise Only
53	22.00	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5mm2 (Phase & Neutral) & 1x1.0 mm2 (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694: and latest amendments) with a 6A flush type SP control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outletLong point above 6m upto 10m from tapping point to out let via switch	Point	582.69	Rupees Five Hundred Eighty Two and Sixty Nine Paise Only
54	700.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS- 694:2010 1 sqmm	Mtr	19.95	Rupees Nineteen and Ninety Five Paise Only
55	700.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. - 2.5 sqmm.	Mtr	44.10	Rupees Forty Four and Ten Paise Only
56	8.00	Supplying 6A flush type socket and 6 A flush type SP switch either surface/flush mounting in existing gang box or in 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required as per IS 1293 and IS 3654 - 6Amps 3/5 Way	Each	154.34	Rupees One Hundred Fifty Four and Thirty Four Paise Only

Signature of the Contractor

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Pa..nahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
69	2.00	Earthing : Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia	Nos	4330.84	Rupees Four Thousand Three Hundred Thirty and Eighty Four Paise Only
70	1.00	Supply and delivery of Centrifugal pumpset at site brand new best make and with discharge duty confirming to ISI standards and its latest amendments. 2 HP, Size 65x50 Head 13M, Discharge 462 LPM	Each	16388.94	Rupees Sixteen Thousand Three Hundred Eighty Eight and Ninety Four Paise Only
71	4.00	Providing & fixing upvc ventilator with Exhaust Turbo speed fan with 5 blades (300mm x 300 mm & above sized fan) with copper motor having mounting arrangements as per direction of Engineer in charge of work	No	2047.31	Rupees Two Thousand Forty Seven and Thirty One Paise Only
72	180.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal dia Pipes	Mtr	367.26	Rupees Three Hundred Sixty Seven and Twenty Six Paise Only
73	144.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 32 mm nominal dia Pipes	Mtr	461.96	Rupees Four Hundred Sixty One and Ninety Six Paise Only
74	2000.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	Ltr	10.39	Rupees Ten and Thirty Nine Paise Only
75	4.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	3559.37	Rupees Three Thousand Five Hundred Fifty Nine and Thirty Seven Paise Only
76	4.00	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete	Each	12962.49	Rupees Twelve Thousand Nine Hundred Sixty Two and Forty Nine Paise Only
77	4.00	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in Granite, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Each	682.54	Rupees Six Hundred Eighty Two and Fifty Four Paise Only
78	60.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 100 mm diameter	Rmtr	336.07	Rupees Three Hundred Thirty Six and Seven Paise Only

Signature of the Contractor

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
79	3040.80	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	279.48	Rupees Two Hundred Seventy Nine and Forty Eight Paise Only
80	457.08	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.Mix 1:3:6 Using 20 mm nominal size graded crushed coarse aggregates	Cum	7179.95	Rupees Seven Thousand One Hundred Seventy Nine and Ninety Five Paise Only
81	53.71	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.All other type of structures	Tonne	91249.01	Rupees Ninety One Thousand Two Hundred Forty Nine and One Paise Only
82	889.87	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	7683.25	Rupees Seven Thousand Six Hundred Eighty Three and Twenty Five Paise Only
83	1460.16	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M20 with OPC cement, with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.	Sqm	2175.39	Rupees Two Thousand One Hundred Seventy Five and Thirty Nine Paise Only
84	422.25	Providing and fixing precast reinforced cement concrete covering slabs of 15Cm thick made of M20 with OPC cement, with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.	Sqm	2689.84	Rupees Two Thousand Six Hundred Eighty Nine and Eighty Four Paise Only
85	151.80	Providing and fixing precast reinforced cement concrete covering slabs of 23Cm thick made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.	Sqm	5288.35	Rupees Five Thousand Two Hundred Eighty Eight and Thirty Five Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Executive Engineer

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
86	365.04	Providing B S slabs of selected quality roughly dressed having a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. as directed by the Engineer in Charge of the work	Sqm	878.77	Rupees Eight Hundred Seventy Eight and Seventy Seven Paise Only
87	365.04	Providing Machine Cutting edges to BS Slab 2.5 cms wide as per Specification (Only chamfered length shall be recorded) Inclusive of all Taxes complete as direction by the Enginer in Charge of the Work	Sqm	409.46	Rupees Four Hundred Nine and Forty Six Paise Only
88	365.04	Providing one line dressing to granite stone slab / granite stone masonry as per specifications as directed by the Engineer in Charge of the work	Sqm	254.08	Rupees Two Hundred Fifty Four and Eight Paise Only
89	2462.22	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work	Nos	532.30	Rupees Five Hundred Thirty Two and Thirty Paise Only
90	22.16	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications Mix 1:2:4 Using 20 mm nominal size graded crushed coarse aggregates	Cum	7209.98	Rupees Seven Thousand Two Hundred Nine and Ninety Eight Paise Only
91	443.20	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	Sqm	125.88	Rupees One Hundred Twenty Five and Eighty Eight Paise Only
92	1266.42	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel	Cum	650.20	Rupees Six Hundred Fifty and Twenty Paise Only
93	2089.44	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work	Cum	109.71	Rupees One Hundred Nine and Seventy One Paise Only
94	311.34	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2955.36	Rupees Two Thousand Nine Hundred Fifty Five and Thirty Six Paise Only
95	1010.64	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications.Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	Cum	6916.64	Rupees Six Thousand Nine Hundred Sixteen and Sixty Four Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Executive Engineer

Name Of Work: Improvements to Roads and Drain at Kogilu, Kogilu Layout, Agrahara, Kattigenahalli, Palanahalli, Chokkanahalli, Surrounding in Ward No. 05, Kogilu and Basavalingappanagara, Jakkur Colony, Sampigehalli Colony, Agrahara Colony Surrounding and Construction of Dr. B R Ambedkar Samudaya Bhavana in Jakkuru in ward No. 06 Jakkuru Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRI. GOPIREDDY	
				In Figures	In Words
96	1010.64	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity andappropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.	Cum	7800.13	Rupees Seven Thousand Eight Hundred and Thirteen Paise Only
97	9367.95	Cost of Haulage Excluding Loading and Unloading Taking output 25 t load and lead 10 km = 100 t.km	T.Km	166.30	Rupees One Hundred Sixty Six and Thirty Paise Only
98	9367.95	Unloading, Loading & Carriage of materials, a). Loading & Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 5.5m3)	Cum	109.25	Rupees One Hundred Nine and Twenty Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92